Abstract Notification dated 26th February 1929.

The attention of the public is invited to the notification calling for tenders printed on page 268 to 269 of Part VI of *Mysore Gazette* of 7th March 1929, for constructing Police Lines of 11 units at Ajjampur, Tarikere Taluk. The last date for receiving tender is 22nd March 1929 till 2-30 P.M.

Abstract Notification dated 26th February 1929.

The attention of the public is invited to the notice calling for tenders for repairing Sri Markandeswaraswami Temple at Khandya, Chikmagalur Taluk, published in detail on pages 266 to 268, Part VI of *Mysore Gazette* of 7th March 1929. The last date for receiving tender is 22nd March 1929, 3 P.M.

B. KRISHNA RAO,
Executive Engineer.

GOVERNMENT OF MYSORE, ELECTRICAL DEPARTMENT.

Dated 27th February 1929.

Attention of the public is invited to the detailed notification published in the *Mysore Gazette*, dated 7th March 1929, page 270, Part VI, inviting tenders for the purchase of about 1,200 steel drums of 45 gallons capacity. Tenders should reach the undersigned on or before 12 Noon of the 30th March 1929. Earnest money required is Rs. 25. Copies of the Notification will be sent on application.

B. RAMANUJA IYENGAR,
Chief Stores Officer,
Chief Electrical Engineer's Office, Bangalore.

CHITALDRUG DISTRICT.

Dated 5th March 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 30th March 1929, for improving Godabanhal Annehal Tank Reg. No. 38 of Chitaldrug Taluk. An approximate estimate of quantities is given below. These quantities are not guaranted. The work should be completed by the end of April 1930.

2. The plan, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chitaldrug between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

4. Each tender must be accompanied by a deposit of Rs. 500 in cash or currency notes as earnest money and be superscribed "Tender for improving Godabanahal Annehal Tank Reg. No. 38 of Chitaldrug Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Shimoga Circle, Shimoga who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenderers, the earnest money on rejected tenders will be returned.

Abstract showing the list of quantities for improving Godabanal Annehal tank Reg. No. 38 of Chitaldrug Taluk.

No.	Items of work	Per	Quantity
	Bund.		
1	Earthwork to bund including watering and tamping with good grips cut at the base to form good joints with the new work.	Cyd.	9,032
2	Removing the apron of right weir and utilising the same for revetment in front.	,,	50
3	Turfing with Mani grass	Syd.	7,070
4	Removing the old revetment and utilising the same to road embankments.	C.yd.	260
5	New stone revetment with lead and etc.	,,	1,180
6	Removing and refixing grade stones with bed slabs including painting.	Each	37
7	Providing new grade stones with bed slabs and etc. ...	,,	3
8	Removing and refixing top width stones	,,	37
9	New bed grade stones	,,	3
10	Removing and refixing Reg. No. stones including painting ...	,,	1
11	Do Gauge stones do ...	,,	1
12	Do B. M. stones to be fixed higher up ...	,,	2
13	Providing Date stone	,,	1
	Sluice.		
14	Making gauge on the gibbet stone with cement and raising the gibbet by 3 feet or R. L. 102·000 1 1/8 wall with burnt brick in surki mortar and cement plastering with burnt stone slabs coping and locking arrangements to the plug rod and clearing silt in front of sluice.		
	Waste Weir.		
15	Earth excavation and utilising the earth to wing bund and etc.	Cyd.	315
16	Filling in foundation with surki concrete	C.ft.	2,096
17	Burn brick in surki mortar	,,	1,600
18	Burnt stone slabs dressed 6" thick with joints, etc., complete ...	S.ft.	447
19	Plastering with nice surki mortar to toe wall wherever necessary	Sqr.	10·35
20	Rough plastering with surki mortar to toe wall wherever necessary.	,,	6·00
21	Rough stone apron with jelly and lead and etc. ...	Cyd.	390
22	Cement pointing to the joints of coping slabs of body and toe walls	Sqrs.	6·00

A. TANDONI RAO,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS.

OFFICE OF THE DIRECTOR OF INDUSTRIES AND COMMERCE, BANGALORE.

Notice No. C. 1. 1183—28-29, dated the 7th March 1929.

The last date for the receipt of Tenders for the supply of Duty Free Salt to the Industrial Concerns in the State, fixed in this office letter No, C1. 1183—28-29, dated the 23rd February 1929, published in the *Mysore Gazette* dated 28th February 1929 on pages 240 and 241 in Part VI, is hereby ALTERED TO '12 NOON OF THE 18TH MARCH 1929'.

C. RANGANATHA RAO SAHIB,
Director.